

**LADWP CII DEMAND RESPONSE PROGRAM**  
POTENTIAL MEASURE GUIDELINE

DR Measures # (DRMs)	Commercial Industrial & Institutional (CII) Measures	Office Building (Property Mgmt.)	Education	Manufacturing	Entertainment	Museum	Aerospace	Healthcare	Retail	Government
DRM-C #1	Elevator Lift Motor Room Space Temperature Setpoint Adjustment (i.e. +2°F   +4°F) - Global Command	✓	✓		✓	✓	✓	✓	✓	✓
DRM-C #2	Air Handling Unit Duct Static Setpoint Adjustment / Reset to 1.0 in IWC	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #3	Pre - Cooling of the Chilled Water Loop   Disable One (1) Water Cooled Chiller	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #4	Pre - Cooling of the Chilled Water Loop   Reset Return Chilled Water Temperature Setpoint	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #5	Parking Garage Lighting Placed Into Egress Mode (Curtail Approx. 40% of Lighting Fixtures)	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #6	Disable EV Parking Garage Charging Point Stations	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #7	Parking Garage Exhaust Fan (s) *Purge Mode Disabled	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #8	Disable Toilet Exhaust (s)	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #9	Disable Parking Garage Escalator (s)	✓	✓		✓	✓	✓	✓	✓	✓
DRM-C #10	Passenger Elevator (s) Curtailment	✓	✓		✓	✓	✓	✓	✓	✓
DRM-C #11	Elevator Vestibule Room Space Temperature Setpoint Adjustment (+2°F   +4°F) - Global Command	✓	✓		✓	✓	✓	✓	✓	✓
DRM-C #12	Overhead Common Corridor Lighting Fixture (s) Curtailment	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #13	Disable Central Hot Water Boiler Plant Circulation Pump Motor (s)	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #14	Dim All Plaza LED Lighting Advertising Boards Down To 75%   50%   30%   15%				✓				✓	
DRM-C #15	Curtail Loading Dock- Exhaust and Supply Air Fan (s)	✓	✓	✓	✓	✓	✓	✓	✓	✓
DRM-C #16	Equipment Processing Delay			✓			✓			
DRM-C #17	Compress Air Plant - Set Point Adjustments			✓			✓	✓		
DRM-C #18	Disable Water Features	✓	✓		✓	✓			✓	✓
DRM-C #19	Global Temperature Set Point Adjustments	✓	✓	✓	✓	✓	✓	✓	✓	✓